

March 8th, 2024

CHELAN COUNTY NATURAL RESOURCE DEPARTMENT
EAGLE CREEK CULVERT REPLACEMENT PROJECT



ADDENDUM NO. 1

To the Contractors, Subcontractors, Planholders and Suppliers:

The following items contain additions, deletions, or modifications to the Plans and/or Specifications. This Addendum forms as a part of the Contract Documents. All updated contract Documents can be found at <https://www.co.chelan.wa.us/natural-resources/pages/current-opportunities>.

Bidders must acknowledge receipt of this Addendum on the Bid Proposal Declaration within the Bid Package.

A. BID SUBMITTAL PACKAGE

A.1 BID PROPOSAL

The Base Bid Schedule A has been revised to reflect the following:

ADDITION OF BID ITEM: The bid schedule for the Base Bid Schedule A is revised to include both “CONTRACTOR DESIGNED BURIED STRUCTURE NO.1” and “CONTRACTOR DESIGNED BURIED STRUCTURE NO.2.” All subsequent bid item numbers are updated to reflect this change.

A copy of the revised bid proposal is attached as Appendix A to this addendum. Please use this revised bid proposal form.

B. SPECIAL PROVISIONS

B.1 DIVISION 2: EARTHWORK

B.1.1 2-09.3 Construction Requirements

This following paragraph is added to the end of this section:

“It is anticipated that excavated material will be suitable for backfill. If the excavated material is determined by the Engineer to be unsuitable for backfill then Common Borrow will be measured per cubic-yard of imported material installed per the plans, and paid under the Force Account “Minor Change” for each bid schedule. Payment will include the full price for hauling, placing, leveling, and compaction and shall be made per cubic-yard of imported material necessary to achieve the final design elevations as shown on the plans and directed by the Contracting officer. “

B.1.2 2-09.4 Measurement

All mention of measurement for “Common Borrow” is deleted from this section.

B.1.3 2-09.5 Payment

All mention of payment for “Common Borrow” is deleted from this section.

B.2 DIVISION 6: STRUCTURES

B.2.1 6-20.3(9) Backfilling

The following paragraph is added to the end of this section:

It is anticipated that excavated material will be suitable for backfill. If the excavated material is determined by the Engineer to be unsuitable for backfill then Common Borrow will be measured per cubic-yard of imported material installed per the plans, and paid under the Force Account “Minor Change” for each bid schedule. Payment will include the full price for hauling, placing, leveling, and compaction and shall be made per cubic-yard of imported material necessary to achieve the final design elevations as shown on the plans and directed by the Contracting officer.

B.2.2 6-20.4 Measurement

This section is revised to read:

“No independent unit of measurement shall apply to the lump sum bid items for “Contractor Designed Buried Structure No. _____” in Bid Schedule A: Base Bid, Schedule B: Additive Bid 1 and Schedule C: Additive Bid 2. “

B.3 DIVISION 8: MISCELLANEOUS CONSTRUCTION


B.3.1 8-02.2 Materials

This section is revised to read:

Seed	9-14.3
Fine Compost	9-14.5
Mulch and Amendments	9-14.6
Biodegradable Erosion Control Blanket	9-14.6

END OF ADDENDUM NO. 1

X



Hannah Pygott, Sr. Natural Resource Specialist
Chelan County Natural Resources Department

APPENDIX A: REVISED BID PROPOSAL FORM

**EAGLE CREEK CULVERT
REPLACEMENT PROJECT**

Addendum NO. 1

BID PROPOSAL FORM

Eagle Creek Culvert Replacement Project

TO: Board of Chelan County Commissioners, Wenatchee, Washington

The Undersigned certify that they have examined the location of the project and read and thoroughly understand the plans, specifications and contract governing the work embraced in this improvement or as much thereof as can be completed with the money available, in accordance with the said plans, specifications, and contract, and the following schedule of rates and prices:

EAGLE CREEK CULVERT REPLACEMENT PROJECT BID SCHEDULE A - BASE BID FOR DOWNS (LOWER) AND DOWNS (UPPER) SITES						
Item	Spec #	Description	Unit	Quantity	Unit Price	Total Price
1	1-09.7	MOBILIZATION	L.S.	1		
2	1-04 SP	MINOR CHANGE	F.A.	2	\$10,000	\$20,000
3	1-05 SP	CONSTRUCTION SURVEYING	L.S.	1		
4	2-01 SP	CLEARING	ACRE	0.14		
5	2.03	CHANNEL EXCAVATION INCL. HAUL	C.Y.	380		
6	2.03	ROADWAY EXCAVATION INCL. HAUL	C.Y.	30		
7	2.09 SP	STRUCTURE EXCAVATION CLASS A INCL. HAUL	C.Y.	810		
8	2.09 SP	SHORING OR EXTRA EXCAVATION CL. A	L.S.	1		
9	2.09 SP	BALLAST	C.Y.	30		
10	2.09 SP	GRAVEL BACKFILL FOR WALLS	C.Y.	50		
11	4-04	CRUSHED SURFACING BASE COURSE	C.Y.	85		
12	5-04	HMA CL. 1/2 IN. PG	TON	60		
13	6-06 SP	PRE-FABRICATED TIMBER GUARDRAIL	L.F.	106		
14	6-20 SP	CONTRACTOR DESIGNED BURIED STRUCTURE NO. 1	L.S.	1		
15	6-20 SP	CONTRACTOR DESIGNED BURIED STRUCTURE NO.2	L.S.	1		
16	8-01	HIGH VISIBILITY FENCE	L.F.	1,480		
17	8-02	FINE COMPOST	C.Y.	30		
18	8-02 SP	SEEDING, AND MULCHING	ACRE	0.10		
19	8-02 SP	BIODEGRADABLE EROSION CONTROL BLANKET	S.Y.	170		
20	8-05 SP	TEMPORARY ACCESS AND STAGING	L.S.	1		
21	8-30 SP	STREAMBED SAND	C.Y.	15		

22	8-30 SP	STREAMBED SEDIMENT	C.Y.	110		
23	8-30 SP	STREAMBED COBBLES - 8 INCH	C.Y.	150		
24	8-30 SP	STREAMBED BOULDER TYPE TWO	EACH	30		
25	8-31 SP	TEMPORARY WATER MANAGEMENT	L.S.	1		
Base Bid Total						

The aforementioned sum is hereby designated the Total Base Bid. The Total Base Bid shall not include Washington State sales tax. Sales tax will be added to the Total Base Bid prior to Contract execution to determine the Contract Sum and sales tax shall be paid by the CONTRACTING AGENCY with each progress payment.

SCHEDULE B– Additive Bid 1 for Loreth Site

The following additive is an integral part of this proposal, and to be responsive, the bidder shall quote for the Base Bid, and also for the following listed Additive Bid Item. The Undersigned certify that they have examined the location of the project and read and thoroughly understand the plans, specifications and contract governing the work embraced in this improvement or as much thereof as can be completed with the money available, in accordance with the said plans, specifications, and contract, and the following schedule of rates and prices:

EAGLE CREEK CULVERT REPLACEMENT PROJECT BID SCHEDULE B - ADDITIVE BID 1 FOR LORETH SITE						
Item	Spec #	Description	Unit	Quantity	Unit Price	Total Price
26	1-09.7	MOBILIZATION	L.S.	1		
27	1-04 SP	MINOR CHANGE	F.A.	1	\$10,000	\$10,000
28	1-05 SP	CONSTRUCTION SURVEYING	L.S.	1		
29	2-01 SP	CLEARING	ACRE	0.07		
30	2.03	CHANNEL EXCAVATION INCL. HAUL	C.Y.	190		
31	2.03	ROADWAY EXCAVATION INCL. HAUL	C.Y.	15		
32	2.09 SP	STRUCTURE EXCAVATION CLASS A INCL. HAUL	C.Y.	220		
33	2.09 SP	SHORING OR EXTRA EXCAVATION CL. A	L.S.	1		
34	2.09 SP	BALLAST	C.Y.	20		
35	2.09 SP	GRAVEL BACKFILL FOR WALLS	C.Y.	30		
36	4-04	CRUSHED SURFACING BASE COURSE	C.Y.	20		
37	5-04	HMA CL. 1/2 IN. PG	TON	35		
38	6-06 SP	PRE-FABRICATED TIMBER GUARDRAIL	L.F.	46		
39	6-20 SP	CONTRACTOR DESIGNED BURIED STRUCTURE NO. 3	L.S.	1		
40	8-01	HIGH VISIBILITY FENCE	L.F.	470		
41	8-02	FINE COMPOST	C.Y.	15		
42	8-02 SP	SEEDING, AND MULCHING	ACRE	0.04		
43	8-02 SP	BIODEGRADABLE EROSION CONTROL BLANKET	S.Y.	70		
44	8-05 SP	TEMPORARY ACCESS AND STAGING	L.S.	1		
45	8-30 SP	STREAMBED SAND	C.Y.	5		
46	8-30 SP	STREAMBED SEDIMENT	C.Y.	50		
47	8-30 SP	STREAMBED COBBLES - 8 INCH	C.Y.	65		
48	8-30 SP	STREAMBED BOULDER TYPE TWO	EACH	15		

49	8-31 SP	TEMPORARY WATER MANAGEMENT	L.S.	1		
Additive Bid 1 Total						

The aforementioned sum is hereby designated the Total Additive Bid Item 1. The Additive Bid Item 1 amount shall not include Washington State sales tax. Sales tax will be added to the Total Additive Bid Item 1 amount prior to Contract execution to determine the Contract Sum and sales tax shall be paid by the CONTRACTING AGENCY with each progress payment.

SCHEDULE C – Additive Bid 2 for Morton Site

The following additive is an integral part of this proposal, and to be responsive, the bidder shall quote for the Base Bid, and also for the following listed Additive Bid Item. The Undersigned certify that they have examined the location of the project and read and thoroughly understand the plans, specifications and contract governing the work embraced in this improvement or as much thereof as can be completed with the money available, in accordance with the said plans, specifications, and contract, and the following schedule of rates and prices:

EAGLE CREEK CULVERT REPLACEMENT PROJECT BID SCHEDULE C - ADDITIVE BID 2 FOR MORTON SITE						
Item	Spec #	Description	Unit	Quantity	Unit Price	Total Price
50	1-09.7	MOBILIZATION	L.S.	1		
51	1-04 SP	MINOR CHANGE	F.A.	1.0	\$10,000	\$10,000
52	1-05 SP	CONSTRUCTION SURVEYING	L.S.	1		
53	2-01 SP	CLEARING	ACRE	0.11		
54	2.03	CHANNEL EXCAVATION INCL. HAUL	C.Y.	410		
55	2.03	ROADWAY EXCAVATION INCL. HAUL	C.Y.	10		
56	2.09 SP	STRUCTURE EXCAVATION CLASS A INCL. HAUL	C.Y.	230		
57	2.09 SP	SHORING OR EXTRA EXCAVATION CL. A	L.S.	1		
58	2.09 SP	BALLAST	C.Y.	10		
59	2.09 SP	GRAVEL BACKFILL FOR WALLS	C.Y.	20		
60	4-04	CRUSHED SURFACING BASE COURSE	C.Y.	15		
61	5-04	HMA CL. 1/2 IN. PG	TON	30		
62	6-06 SP	PRE-FABRICATED TIMBER GUARDRAIL	L.F.	46		
63	6-20 SP	CONTRACTOR DESIGNED BURIED STRUCTURE NO. 4	L.S.	1		
64	8-01	HIGH VISIBILITY FENCE	L.F.	320		
65	8-02	FINE COMPOST	C.Y.	20		
66	8-02 SP	SEEDING, AND MULCHING	ACRE	0.06		
67	8-02 SP	BIODEGRADABLE EROSION CONTROL BLANKET	S.Y.	175		
68	8-05 SP	TEMPORARY ACCESS AND STAGING	L.S.	1		
69	8-30 SP	STREAMBED SAND	C.Y.	10		
70	8-30 SP	STREAMBED SEDIMENT	C.Y.	65		
71	8-30 SP	STREAMBED COBBLES - 8 INCH	C.Y.	100		
72	8-30 SP	STREAMBED BOULDER TYPE ONE	EACH	540		

73	8-30 SP	STREAMBED BOULDER TYPE TWO	EACH	24		
74	8-31 SP	TEMPORARY WATER MANAGEMENT	L.S.	1		
Additive Bid 2 Total						

The aforementioned sum is hereby designated the Total Additive Bid Item 2. The Additive Bid Item 2 amount shall not include Washington State sales tax. Sales tax will be added to the Total Additive Bid Item 2 amount prior to Contract execution to determine the Contract Sum and sales tax shall be paid by the CONTRACTING AGENCY with each progress payment.

TOTALS

SCHEDULE A: BASE BID TOTAL (EXCLUDING WSST)	
COMBINED TOTAL SCHEDULE A: BASE BID + SCHEDULE B: ADDITIVE BID 1 (EXCLUDING WSST)	
TOTAL COMBINED BID (SCHEDULE A: BASE BID + SCHEDULE B: ADDITIVE BID 1 + SCHEDULE C: ADDITIVE BID 2) (EXCLUDING WSST)	

The aforementioned sums are hereby designated the Base Bid Total, Combined Total Schedule A and Schedule B, and Total Combined Bid. The Base Bid, and Additives shall not include Washington State sales tax. Sales tax will be added to the Total Base Bid prior to Contract execution to determine the Contract Sum and sales tax shall be paid by the CONTRACTING AGENCY with each progress payment.

PRINT BIDDER NAME

DATE

SIGNATURE OF PRINCIPAL OR OFFICER