



Chelan County - Wenatchee - Douglas County - East Wenatchee

# Downs Road Stormwater Improvements

*Last Updated: January 22, 2015*

**Status: Complete**

**Estimated Completion: Fall 2014**

**Project Details:** During large rain events, stormwater runoff would bypass the existing detention pond and flow over the county road causing damage to the existing pavement and causing safety concerns. Chelan County's stormwater utility funded the design and installation of a new catch basin and culvert on the south side of the roadway to convey the stormwater into the pond. Additionally, approximately 350 feet of roadside ditch that was eroded was reestablished and armored with quarry spalls.

The project was awarded to Rayfield Brothers with a bid of \$21,000.



Inadequate facilities created damage and safety issues