

MONITOR SIDE CHANNEL RESTORATION

CHELAN COUNTY NATURAL RESOURCES DEPARTMENT





| SHEET LIST | | | | |
|-----------------|--------------------------------------|--|--|--|
| SHEET NUMBER | SHEET TITLE | | | |
| 1 | COVER SHEET | | | |
| 2 | GENERAL NOTES | | | |
| 3 | LEGEND | | | |
| 4 | PROPOSED CONDITIONS — OVERALL PLAN | | | |
| 5 | PROPOSED CONDITIONS - SITE 1 | | | |
| 6 | PROPOSED CONDITIONS - SITE 2 | | | |
| 7 | TYPE 1 ELJ | | | |
| 8 | TYPE 1 ELJ LAYERING PLANS 1 | | | |
| 9 | TYPE 1 ELJ LAYERING PLANS 2 | | | |
| 10 | TYPE 2 ELJ | | | |
| 11 | TYPE 2 ELJ LAYERING PLANS 1 | | | |
| 12 | TYPE 2 ELJ LAYERING PLANS 2 | | | |
| 13 | TYPE 3 ELJ | | | |
| 14 | TYPE 3 ELJ LAYERING PLANS 1 | | | |
| 15 | TYPE 3 ELJ LAYERING PLANS 2 | | | |
| 16 | TYPE 4 ELJ | | | |
| 17 | TYPE 4 ELJ LAYERING PLANS 1 | | | |
| 18 | TYPE 4 ELJ LAYERING PLANS 2 | | | |
| 19 | ELJ DETAILS 1 | | | |
| 20 | ELJ DETAILS 2 | | | |
| 21 | ACCESS, STAGING, AND DEWATERING PLAN | | | |
| 22 | SITE ACCESS AND DEWATERING DETAILS | | | |

CONTACT INFORMATION


NATURAL SYSTEMS DESIGN, INC

1900 N NORTHLAKE WAY, SUITE 211 SEATTLE, WA 98103 (206) 834-0175

CHELAN COUNTY NATURAL RESOURCE DEPARTMENT

411 WASHINGTON STREET, SUITE 201 WENATCHEE, WA 98801 PHONE: (509) 667-6533









| NAME OR | INITIALS AND DATE | GEOGRAPH | IC INFORMATION |
|----------|-------------------|-----------|----------------|
| DESIGNED | N. TRUSCOTT | LATITUDE | 47*29'33"N |
| CHECKED | W.J. SMITH | LONGITUDE | 120°25'15"W |
| DRAWN | G. MATSUMOTO | TN/SC/RG | T23N/S14/R19E |
| CHECKED | N. TRUSCOTT | DATE | MARCH 26, 2021 |

VICINITY MAP

SCALE: 1" = 1 mile

MONITOR SIDE CHANNEL RESTORATION

COVER SHEET

SHEET 1 OF 22

- 2. NATURAL SYSTEMS DESIGN HEREAFTER REFERRED TO AS "DESIGN ENGINEER" IS RESPONSIBLE FOR THE PREPARATION OF THESE ORIGINAL PLANS AND ASSOCIATED SPECIFICATIONS; AND WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGE, OR USE, OF THESE PLANS WHICH INCLUDES ALTERATION. DELETION. OR EDITING OF THIS DOCUMENT WITHOUT EXPLICIT WRITTEN PERMISSION FROM THE DESIGN ENGINEER. ANY OTHER UNAUTHORIZED USE OF THIS DOCUMENT
- 3. MINOR MODIFICATIONS ARE EXPECTED TO SUIT JOB SITE DIMENSIONS OR CONDITIONS. SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. THE OWNER, DESIGN ENGINEER AND APPROPRIATE REGULATORY AGENCIES SHALL BE NOTIFIED OF ANY OWNER-AUTHORIZED CHANGE RESULTING IN MORE THAN A 10% DESIGN CHANGE OF PROPOSED FOOTPRINT OR THAT SIGNIFICANTLY AFFECTS THE INTENDED BENEFIT OR FUNCTION OF A PROJECT ELEMENT.
- 4. THE LOCATION OF ALL FEATURES SHOWN IS APPROXIMATE.
- 5. THE CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; AND FURTHER AGREES THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS IN ACCORDANCE WITH THE PROVISIONS OUTLINED BY THE PROJECT CONTRACT AND SPECIFICATIONS.
- 6. ALL IMPROVEMENTS SHALL BE ACCOMPLISHED UNDER THE APPROVAL, INSPECTION, AND TO THE SATISFACTION OF THE OWNER. IMPROVEMENT CONSTRUCTION SHALL COMPLY WITH THESE PLANS AND THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT) STANDARD PLANS. ALL REFERENCES TO THE "STANDARD SPECIFICATIONS" SHALL MEAN THE WSDOT STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION, CURRENT EDITION. CONSTRUCTION NOT SPECIFIED ON THESE PLANS SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS. THE CONTRACTOR IS OBLIGATED TO BE FAMILIAR WITH APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS NOT DISCUSSED IN THE GENERAL NOTES. THE CONTRACT SPECIAL PROVISIONS SHALL SUPERSEDE THOSE OF THE STANDARD SPECIFICATIONS WHERE DISCREPANCIES OCCUR.
- 7. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND SUBCONTRACTOR(S) TO EXAMINE THE PROJECT SITE PRIOR TO THE OPENING OF BID PROPOSALS. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED. SUCH AS THE NATURE AND LOCATION OF THE WORK; AND THE GENERAL AND LOCAL CONDITIONS, PARTICULARLY THOSE AFFECTING THE AVAILABILITY OF TRANSPORTATION, THE DISPOSAL, HANDLING, AND STORAGE OF MATERIALS, AVAILABILITY OF LABOR, WATER, ELECTRICITY, ROADS, THE UNCERTAINTIES OF WEATHER, THE CONDITIONS OF THE GROUND, SURFACE AND SUBSURFACE MATERIALS, GROUNDWATER, THE EQUIPMENT AND FACILITIES NEEDED FOR AND DURING THE PERFORMANCE OF THE WORK, AND THE COSTS THEREOF. ANY FAILURE BY THE CONTRACTOR AND SUBCONTRACTOR(S) TO ACQUAINT THEMSELVES WITH ALL THE AVAILABLE INFORMATION WILL NOT RELIEVE THE CONTRACTOR AND SUBCONTRACTOR(S) FROM RESPONSIBILITY FOR PROPERLY ESTIMATING THE DIFFICULTY AND COST OF SUCCESSFULLY PERFORMING THE WORK.
- 8. THE CONTRACTOR IS RESPONSIBLE FOR REVIEWING THE CONTRACT DOCUMENTS AND FOR ALL SUBMITTALS REQUIRED TO THE OWNER FOR REVIEW AND ACCEPTANCE.

PERMIT NOTES

- 1. EVERY REASONABLE EFFORT SHALL BE MADE TO CONDUCT THE ACTIVITIES SHOWN IN THESE PLANS IN A MANNER THAT MINIMIZES THE ADVERSE IMPACT ON WATER QUALITY, FISH AND WILDLIFE, AND THE NATURAL ENVIRONMENT.
- 2. ALL WORK SHALL BE IN COMPLIANCE WITH PERMIT CONDITIONS ISSUED BY PERTINENT REGULATORY AGENCIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE COPIES OF ALL PERMITS ON THE JOB SITE, AND TO UNDERSTAND AND COMPLY WITH ALL PERMIT CONDITIONS.
- 3. ALL WORK THAT DISTURBS THE SUBSTRATE, BANK, OR SHORE OF A WATERS OF THE STATE THAT CONTAINS FISH LIFE SHALL BE CONDUCTED ONLY DURING THE WORK PERIOD FOR THAT WATERBODY AS ALLOWED BY RELEVANT PROJECT PERMITS. THOSE PORTIONS OF THE PROJECT WORK THAT OCCUR OUTSIDE OR ABOVE THE ORDINARY HIGH WATER MARK (ABOVE THE USACE JURISDICTIONAL LINE) ARE NOT SUBJECT TO THE WORK PERIODS DESCRIBED ABOVE UNLESS SPECIFIED IN THE RELEVANT PERMITS.
- 4. ALL ACTIVITIES THAT INVOLVE WORK ADJACENT TO, OR WITHIN THE WETTED CHANNEL SHALL, AT ALL TIMES, REMAIN CONSISTENT WITH ALL APPLICABLE WATER QUALITY STANDARDS; EFFLUENT LIMITATION; AND STANDARDS OF PERFORMANCE, PROHIBITIONS, PRETREATMENT STANDARDS, AND MANAGEMENT PRACTICES ESTABLISHED PURSUANT TO THE CLEAN WATER ACT OR PURSUANT TO APPLICABLE STATE AND LOCAL LAW.

- 5. IF AT ANY TIME, AS A RESULT OF PROJECT ACTIVITIES, FISH ARE OBSERVED IN DISTRESS, A FISH KILL OCCURS, OR WATER QUALITY PROBLEMS DEVELOP (INCLUDING EQUIPMENT LEAKS OR SPILLS), OPERATIONS SHALL CEASE AND THE OWNER SHALL BE NOTIFIED IMMEDIATELY
- 6. IF, DURING CONSTRUCTION, ARCHAEOLOGICAL REMAINS ARE ENCOUNTERED, CONSTRUCTION IN THE VICINITY SHALL BE HALTED, AND THE STATE OFFICE OF HISTORIC PRESERVATION AND THE OWNER SHALL BE NOTIFIED IMMEDIATELY.

SURVEY NOTES


- 1. UNLESS NOTED OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SURVEY MONUMENTS AND OTHER SURVEY MARKERS DURING
- 2. THE CONTRACTOR SHALL MAINTAIN A SET OF PLANS ON THE JOB SHOWING "AS—CONSTRUCTED" CHANGES MADE TO DATE. UPON COMPLETION OF THE PROJECT, THE CONTRACTOR SHALL SUPPLY TO OWNER A SET OF PLANS, MARKED UP TO THE SATISFACTION OF THE OWNER, REFLECTING THE AS-CONSTRUCTED MODIFICATIONS
- 3. LIDAR FOR THIS PROJECT WAS COLLECTED IN 2015. THE VERTICAL DATUM IS NAVD88 AND THE HORIZONTAL DATUM IS NAD83 (2011). ALL ELEVATIONS AND DISTANCES SHOWN ARE U.S. SURVEY

EROSION. SEDIMENT CONTROL AND WATER MANAGEMENT NOTES


- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING ALL TEMPORARY EROSION CONTROL MEASURES. THE EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND PERFORMANCE OF THE TEMPORARY EROSION CONTROL MEASURES THROUGHOUT THE DURATION OF THE PROJECT.
- 2. A TEMPORARY EROSION AND SEDIMENT CONTROL PLAN SHALL BE DEVELOPED BY THE CONTRACTOR AND SUBMITTED FOR APPROVAL BY OWNER BEFORE ANY CONSTRUCTION MAY BEGIN. THE SEDIMENT AND EROSION CONTROL PLAN SHALL IDENTIFY BEST MANAGEMENT PRACTICES TO ENSURE THAT THE TRANSPORT OF SEDIMENT TO SURFACE WATERS, DRAINAGE SYSTEMS, AND ADJACENT PROPERTIES IS MINIMIZED.
- 3. ACTIVITIES SHALL BE DESIGNED AND CONSTRUCTED TO AVOID AND MINIMIZE ADVERSE IMPACTS TO WATERS OF THE UNITED STATES TO THE MAXIMUM EXTENT PRACTICAL THROUGH THE USE OF PRACTICAL ALTERNATIVES. ALTERNATIVES THAT SHALL BE CONSIDERED INCLUDE THOSE THAT MINIMIZE THE NUMBER AND EXTENT OF IN-WATER WORK AND EQUIPMENT CROSSINGS OF WETTED CHANNELS.
- 4. AT NO TIME SHALL SEDIMENT-LADEN WATER BE DISCHARGED OR PUMPED DIRECTLY INTO THE SUBJECT RIVER, STREAM, OR WETLAND, WATER SHALL BE DISCHARGED IN ACCORDANCE WITH REQUIREMENTS SET FORTH IN THE PROJECT PERMITS AND/OR SPECIFICATIONS.
- 5. IF HIGH WATER LEVEL CONDITIONS THAT CAUSE SILTATION OR EROSION ARE ENCOUNTERED DURING CONSTRUCTION, WORK SHALL STOP UNTIL THE WATER LEVEL SUBSIDES.
- 6. PERMIT CONDITIONS CONTAIN SPECIFIC REQUIREMENTS FOR THE CONTROL OF EROSION AND TURBIDITY FROM PROJECT OPERATIONS. TURBIDITY WILL BE MONITORED ON A FREQUENT BASIS BY THE PROJECT MANAGEMENT AND INSPECTION STAFF ON-SITE. TURBIDITY AMOUNTS IN EXCESS OF THE PERMITTED CONCENTRATIONS AND/OR DURATIONS WILL CAUSE WORK TO BE STOPPED UNTIL IMPROVED PRACTICES ARE IN EFFECT AND THE PROBLEMS CONTROLLED. THE CONTRACTOR IS COMPLETELY RESPONSIBLE FOR ANY PROJECT DELAYS THAT OCCUR BY NATURE OF THIS FAILURE TO ADEQUATELY CONTAIN SEDIMENT ON-SITE.
- 7. CONTRACTOR SHALL LIMIT MACHINERY MOVEMENT TO CONSTRUCTION AREAS DEFINED ON SITE PLAN OR IDENTIFIED AS ACCEPTABLE BY THE CONTRACTING OFFICER.
- 8. ALL EXTERNAL GREASE AND OIL SHALL BE PRESSURE-WASHED OFF THE EQUIPMENT PRIOR TO TRANSPORT TO THE SITE.
- 9. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT NO PETROLEUM PRODUCTS, HYDRAULIC FLUID, SEDIMENTS, SEDIMENT-LADEN WATER, CHEMICALS, OR ANY OTHER TOXIC OR DELETERIOUS MATERIALS ARE ALLOWED TO ENTER OR LEACH INTO THE SUBJECT RIVER STREAM OR WETLAND
- 10. THE CONTRACTOR SHALL HAVE AN EMERGENCY SPILL KIT ON-SITE AT ALL TIMES.
- 11. NO TREES OR WETLAND VEGETATION SHALL BE REMOVED UNLESS THEY ARE FLAGGED FOR REVIEW AND SUBSEQUENTLY APPROVED FOR REMOVAL BY THE CONTRACTING OFFICER. ALL TREES CONFLICTING WITH GRADING SHALL BE REMOVED. NO GRADING SHALL TAKE PLACE WITHIN THE DRIP LINE OF TREES TO REMAIN UNLESS OTHERWISE APPROVED.
- 12. FOLLOWING CONSTRUCTION SEEDING, MULCHING, AND PLANTING WILL BE COMPLETED BY OTHERS. THIS DOES NOT RELEASE THE CONTRACTOR FROM THE RESPONSIBILITY OF APPLICABLE STABILIZATION MEASURES IDENTIFIED IN THE PLANS, SPECIFICATIONS, OR THE APPROVED TESC


CONSTRUCTION NOTES

- 1. CONTRACT DOCUMENTS INCLUDE THESE PLANS.
- 2. CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, AND LABOR NECESSARY TO COMPLETE ALL WORK AS INDICATED IN THE CONTRACT DOCUMENTS.
- 3. CONSTRUCTION HOURS SHALL BE WEEKDAYS BETWEEN 7:00 A.M. AND 6:30 P.M. UNLESS PRIOR APPROVAL IS RECEIVED FROM THE OWNER.
- 4. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE OWNER PRIOR TO PROCEEDING WITH THE WORK.
- 5. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY INDICATED OTHERWISE BY THE OWNER OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE
- ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES.
- 7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING THE BEST SKILLS AND ATTENTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT.
- 8. THE CONTRACTOR SHALL MAKE ALL NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, ROADWAYS, DRAINAGE WAYS, PRIVATE BRIDGES, CULVERTS, AND VEGETATION UNTIL SUCH ITEMS ARE TO BE DISTURBED OR REMOVED AS INDICATED ON THE CONTRACT DOCUMENTS.
- 9. THE CONTRACTOR SHALL KEEP THE JOB SITE CLEAN AND HAZARD FREE. CONTRACTOR SHALL DISPOSE OF ALL DIRT, DEBRIS, AND RUBBISH FOR THE DURATION OF THE WORK. UPON COMPLETION OF WORK, CONTRACTOR SHALL REMOVE ALL MATERIAL AND EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY
- 10. NOTES AND DETAILS ON THE PLANS SHALL TAKE PRECEDENCE OVER GENERAL NOTES HEREIN.
- 11. DIMENSIONAL CALLOUTS SHALL TAKE PRECEDENCE OVER SCALES SHOWN ON THE PLANS.
- 12. THE PLANS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF ALL CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURES, WORKS, AND THE PUBLIC DURING CONSTRUCTION.
- 13. MATERIAL SHALL NOT BE STORED OUTSIDE OF IDENTIFIED STAGING AREAS. THE CONTRACTOR SHALL USE ONLY DESIGNATED SITES FOR STORAGE OF EQUIPMENT AND MATERIALS AS SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SECURITY OF ALL EQUIPMENT AND MATERIALS.









MONITOR SIDE CHANNEL RESTORATION


GENERAL NOTES

FINAL DESIGN

2021

26,


ar



SAND BAG COFFERDAM $\frac{5}{22}$

PUMP DISCHARGE OUTLET

DEWATERING PUMP



CONTROL POINT LOCATION

FILL SLOPE LINE

>---- EXCAVATION SLOPE LINE



26, 2021 FINAL DESIGN


Mar


BOULDER CLUSTER


WILLOW TRENCH ()


GEOGRAPHIC INFORMATION


TITUDE 47*29'33"N ONGITUDE 120°25'15"W TN/SC/RG T23N/S14/R19E MARCH 26, 2021 MONITOR SIDE CHANNEL














TYPE 1 ELJ PERSPECTIVE

NOTES

10'

SCALE: 1"=5'-0"

1. ALL LOGS SHALL BE DOUGLAS FIR, PONDEROSA PINE, WESTERN RED CEDAR, OR WESTERN LARCH TREES.

TYPE 1 ELJ PROFILE

2. ALL POSTS SHALL BE DOUGLAS FIR. POSTS SHALL BE FREE FROM DEFECTS, CRACKS, AND SPLITTING AT THE TIME OF INSTALLATION. POSTS SHALL HAVE A MINIMUM DBH OF 20 INCHES EXCLUDING BARK.


SCALE: 1"=5'-0

- 3. LOGS WITH ROOTWADS SHALL HAVE A DIAMETER AS SHOWN MEASURED AT DBH.
- 4. THE CONTRACTOR SHALL PLACE LOGS AS ILLUSTRATED ON THIS SHEET UNLESS DIRECTED OTHERWISE BY THE CONTRACTING OFFICER.
- 5. SOIL EXCAVATED DURING CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED AND BACKFILLED AS NECESSARY DURING CONSTRUCTION. EXCESS MATERIAL SHALL BE EVENLY DISTRIBUTED IN THE LEE OF THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 6. RACKING LOGS SHALL CONSIST OF TREES WITH BRANCHES HAVING A BASE DIAMETER OF 6-12 INCHES AND A LENGTH OF 20-40 FT. TOTAL NUMBER OF RACKING LOGS PER STRUCTURE SHALL BE 60 PIECES. RACKING MATERIAL SHALL BE PLACED AS SPECIFIED IN THE CONSTRUCTION SEQUENCE TO ENSURE THAT RACKING MATERIAL EXTENDS THROUGH THE STRUCTURE AND IS PINNED BY SUBSEQUENT LAYERS. SLASH MATERIAL SHALL CONSIST OF LIMBS AND BRANCHES AND A BASE DIAMETER BETWEEN 1 AND 3 INCHES. TOTAL SLASH MATERIAL QUANTITY SHALL BE 20 CUBIC YARDS. SLASH MATERIAL SHALL BE PLACED AS DIRECTED BY THE CONTRACTING OFFICER.
- 7. EXTENT AND LOCATION OF THE SCOUR POOL IS APPROXIMATE AND TO BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER.
- 8. EXISTING WOODY MATERIAL AT THE STRUCTURE CONSTRUCTION SITE SHALL BE MOVED OR PROTECTED FROM CONSTRUCTION ACTIVITIES AND THEN INCORPORATED INTO THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 9. FOR ROOTWAD DIMENSIONING REQUIREMENTS SEE $\begin{pmatrix} 2 \\ 20 \end{pmatrix}$

TYPE 1 ELJ MATERIALS SCHEDULE

| | | | | 9 1117 (1 =1 (1) (= (| 3 331123322 |
|----------------------------------|-----------------|-----------------|------------------|---------------------------|--|
| LOG ID | DIA (INCHES) | LENGTH * (FEET) | ROOTWAD (Y/N) | QUANTITY PER STRUCTURE | NOTES |
| RD-4 | 20-22 | 40 | Υ | 3 | |
| RD-3P | 20 MIN | 30 | Y | 2 | VERTICAL POST |
| RD-3Pb | 20 MIN | 30 | Y | 4 | BATTER POST INSTALLED 15 TO 20 DEGREES FROM VERTICAL |
| RE-3 | 16-18 | 30 | Y | 3 | |
| E-3 | 16-18 | 30 | N | 4 | |
| RACKING BUNDLE | 48 | 30 | | 1 | |
| RACKING | 6-12 | 20-40 | Y/N | 60 | |
| SLASH | | | | 20 CY | |
| * TOTAL LENGTH INCLUDING ROOTWAD | | | | | |






TYPE 1 ELJ PLAN

SCALE: 1" = 5'





MONITOR SIDE CHANNEL RESTORATION


TYPE 1 ELJ


TYPE 1 ELJ DETAILS


SCALE: AS NOTED

7

SHEET **7** OF **22**










TYPE 1 ELJ POST DIMENSIONING PLAN (SCALE: 1" = 5'

26, 2021 FINAL DESIGN

Mar







TYPE 2 ELJ PERSPECTIVE

NOTES

- 1. ALL LOGS SHALL BE DOUGLAS FIR, PONDEROSA PINE, WESTERN RED CEDAR, OR WESTERN LARCH TREES.
- 2. ALL POSTS SHALL BE DOUGLAS FIR. POSTS SHALL BE FREE FROM DEFECTS, CRACKS, AND SPLITTING AT THE TIME OF INSTALLATION. POSTS SHALL HAVE A MINIMUM DBH OF 20 INCHES EXCLUDING BARK.


SCALE: 1"=5'-0'

- 3. LOGS WITH ROOTWADS SHALL HAVE A DIAMETER AS SHOWN MEASURED AT DBH.
- 4. THE CONTRACTOR SHALL PLACE LOGS AS ILLUSTRATED ON THIS SHEET UNLESS DIRECTED OTHERWISE BY THE CONTRACTING OFFICER.
- 5. SOIL EXCAVATED DURING CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED AND BACKFILLED AS NECESSARY DURING CONSTRUCTION. EXCESS MATERIAL SHALL BE EVENLY DISTRIBUTED IN THE LEE OF THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 6. RACKING LOGS SHALL CONSIST OF TREES WITH BRANCHES HAVING A BASE DIAMETER OF 6-12 INCHES AND A LENGTH OF 20-40 FT. TOTAL NUMBER OF RACKING LOGS PER STRUCTURE SHALL BE 60 PIECES. RACKING MATERIAL SHALL BE PLACED AS SPECIFIED IN THE CONSTRUCTION SEQUENCE TO ENSURE THAT RACKING MATERIAL EXTENDS THROUGH THE STRUCTURE AND IS PINNED BY SUBSEQUENT LAYERS. SLASH MATERIAL SHALL CONSIST OF LIMBS AND BRANCHES AND A BASE DIAMETER BETWEEN 1 AND 3 INCHES. TOTAL SLASH MATERIAL QUANTITY SHALL BE 20 CUBIC YARDS. SLASH MATERIAL SHALL BE PLACED AS DIRECTED BY THE CONTRACTING OFFICER.
- 7. EXTENT AND LOCATION OF THE SCOUR POOL IS APPROXIMATE AND TO BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER.
- EXISTING WOODY MATERIAL AT THE STRUCTURE CONSTRUCTION SITE SHALL BE MOVED OR PROTECTED FROM CONSTRUCTION ACTIVITIES AND THEN INCORPORATED INTO THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 9. FOR ROOTWAD DIMENSIONING REQUIREMENTS SEE $(\frac{2}{20})$


TYPE 2 FLI MATERIALS SCHEDULE

| | | | | | 3 SUILDULL |
|-------------------|---------------|----------|---------|--------------|--|
| LOG ID | DIA | LENGTH * | ROOTWAD | QUANTITY PER | NOTEC |
| | (INCHES) | (FEET) | (Y/N) | STRUCTURE | NOTES |
| RD-4 | 20-22 | 40 | Y | 1 | |
| RE-3 | 20-22 | 30 | Y | 4 | |
| RD-3Pb | 20 MIN | 30 | Y | 4 | BATTER POST INSTALLED 15 TO 20 DEGREES FROM VERTICAL |
| RACKING BUNDLE | 48 | 30 | | 1 | |
| RACKING | 6-12 | 20-40 | Y/N | 60 | |
| SLASH | | | | 20 CY | |
| BOULDER COLLAR | 36 | | | 10 EA | |
| * TOTAL LENGTH IN | ICLUDING ROOT | WAD | | | |









MONITOR SIDE CHANNEL RESTORATION


TYPE 2 ELJ


TYPE 2 ELJ DETAILS


SCALE: AS NOTED

10


SHEET 10 OF 22









TYPE 3 ELJ PLAN





TYPE 3 ELJ PROFILE



TYPE 3 ELJ PERSPECTIVE


<u>NOTES</u>

- 1. ALL LOGS SHALL BE DOUGLAS FIR, PONDEROSA PINE, WESTERN RED CEDAR, OR WESTERN LARCH TREES.
- 2. ALL POSTS SHALL BE DOUGLAS FIR. POSTS SHALL BE FREE FROM DEFECTS, CRACKS, AND SPLITTING AT THE TIME OF INSTALLATION. POSTS SHALL HAVE A MINIMUM DBH OF 20 INCHES EXCLUDING BARK.
- 3. LOGS WITH ROOTWADS SHALL HAVE A DIAMETER AS SHOWN MEASURED AT DBH.
- 4. THE CONTRACTOR SHALL PLACE LOGS AS ILLUSTRATED ON THIS SHEET UNLESS DIRECTED OTHERWISE BY THE CONTRACTING OFFICER.
- 5. SOIL EXCAVATED DURING CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED AND BACKFILLED AS NECESSARY DURING CONSTRUCTION. EXCESS MATERIAL SHALL BE EVENLY DISTRIBUTED IN THE LEE OF THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 6. RACKING LOGS SHALL CONSIST OF TREES WITH BRANCHES HAVING A BASE DIAMETER OF 6-12 INCHES AND A LENGTH OF 20-40 FT. TOTAL NUMBER OF RACKING LOGS PER STRUCTURE SHALL BE 40 PIECES. RACKING MATERIAL SHALL BE PLACED AS SPECIFIED IN THE CONSTRUCTION SEQUENCE TO ENSURE THAT RACKING MATERIAL EXTENDS THROUGH THE STRUCTURE AND IS PINNED BY SUBSEQUENT LAYERS. SLASH MATERIAL SHALL CONSIST OF LIMBS AND BRANCHES AND A BASE DIAMETER BETWEEN 1 AND 3 INCHES. TOTAL SLASH MATERIAL QUANTITY SHALL BE 15 CUBIC YARDS. SLASH MATERIAL SHALL BE PLACED AS DIRECTED BY THE CONTRACTING OFFICER.
- 7. EXTENT AND LOCATION OF THE SCOUR POOL IS APPROXIMATE AND TO BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER.
- 8. EXISTING WOODY MATERIAL AT THE STRUCTURE CONSTRUCTION SITE SHALL BE MOVED OR PROTECTED FROM CONSTRUCTION ACTIVITIES AND THEN INCORPORATED INTO THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 9. FOR ROOTWAD DIMENSIONING REQUIREMENTS SEE

TYPE 3 FLU MATERIALS SCHEDULE


| | | 1 1 1 | | | 3 SCHEDULL |
|----------------------------------|-----------------|-----------------|------------------|---------------------------|--|
| LOG ID | DIA (INCHES) | LENGTH * (FEET) | ROOTWAD (Y/N) | QUANTITY PER STRUCTURE | NOTES |
| RD-3Pb | 20 MIN | 30 | Y | 3 | INSTALL BATTER POSTS AT 15 TO 20 DEGREES FROM VERTICAL |
| RE-3 | 16-18 | 30 | Y | 5 | |
| E-3 | 16-18 | 30 | N | 3 | |
| RACKING BUNDLE | 48 | 30 | | 1 | |
| RACKING | 6-12 | 20-40 | Y/N | 40 | |
| SLASH | | | | 15 CY | |
| * TOTAL LENGTH INCLUDING ROOTWAD | | | | | |







SCALE: 1"=5'-0



MONITOR SIDE CHANNEL RESTORATION


TYPE 3 ELJ


TYPE 3 ELJ DETAILS


SCALE: AS NOTED


13

SHEET 13 OF 22











MONITOR SIDE CHANNEL **RESTORATION**


CHECKED N. TRUSCOTT

MARCH 26, 2021

TYPE 3 ELJ LAYERING PLANS







NOTES

- 1. ALL LOGS SHALL BE DOUGLAS FIR, PONDEROSA PINE, WESTERN RED CEDAR, OR WESTERN LARCH TREES.
- 2. ALL POSTS SHALL BE DOUGLAS FIR. POSTS SHALL BE FREE FROM DEFECTS, CRACKS, AND SPLITTING AT THE TIME OF INSTALLATION. POSTS SHALL HAVE A MINIMUM DBH OF 20 INCHES

SCALE: 1"=5'-0"


- 3. LOGS WITH ROOTWADS SHALL HAVE A DIAMETER AS SHOWN MEASURED AT DBH,
- 4. THE CONTRACTOR SHALL PLACE LOGS AS ILLUSTRATED ON THIS SHEET UNLESS DIRECTED OTHERWISE BY THE CONTRACTING OFFICER.
- 5. SOIL EXCAVATED DURING CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED AND BACKFILLED AS NECESSARY DURING CONSTRUCTION. EXCESS MATERIAL SHALL BE EVENLY DISTRIBUTED IN THE LEE OF THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 6. RACKING LOGS SHALL CONSIST OF TREES WITH BRANCHES HAVING A BASE DIAMETER OF 6-12 INCHES AND A LENGTH OF 20-40 FT. TOTAL NUMBER OF RACKING LOGS PER STRUCTURE SHALL BE 50 PIECES. RACKING MATERIAL SHALL BE PLACED AS SPECIFIED IN THE CONSTRUCTION SEQUENCE TO ENSURE THAT RACKING MATERIAL EXTENDS THROUGH THE STRUCTURE AND IS PINNED BY SUBSEQUENT LAYERS. SLASH MATERIAL SHALL CONSIST OF LIMBS AND BRANCHES AND A BASE DIAMETER BETWEEN 1 AND 3 INCHES. TOTAL SLASH MATERIAL QUANTITY SHALL BE 10 CUBIC YARDS. SLASH MATERIAL SHALL BE PLACED AS DIRECTED BY THE CONTRACTING OFFICER.
- 7. EXTENT AND LOCATION OF THE SCOUR POOL IS APPROXIMATE AND TO BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER.
- 8. EXISTING WOODY MATERIAL AT THE STRUCTURE CONSTRUCTION SITE SHALL BE MOVED OR PROTECTED FROM CONSTRUCTION ACTIVITIES AND THEN INCORPORATED INTO THE STRUCTURE AS DIRECTED BY THE CONTRACTING OFFICER.
- 9. FOR ROOTWAD DIMENSIONING REQUIREMENTS SEE



TYPE 4 ELJ MATERIALS SCHEDULE

| DIA (INCHES) | LENGTH * (FEET) | ROOTWAD (Y/N) | QUANTITY PER STRUCTURE | NOTES | |
|----------------------------------|--|------------------------|--|--|--|
| 20-22 | 40 | Y | 4 | | |
| 16-18 | 30 | Y | 1 | | |
| 20-22 | 30 | Y | 3 | VERTICAL POST | |
| 16-18 | 25 | Ν | 1 | | |
| 48 | 30 | | 1 | | |
| 6-12 | 20-40 | Y/N | 50 | | |
| | | | 10 CY | | |
| * TOTAL LENGTH INCLUDING ROOTWAD | | | | | |
| | (INCHES) 20-22 16-18 20-22 16-18 48 6-12 | (INCHES) (FEET) 20-22 | (INCHES) (FEET) (Y/N) 20-22 40 Y 16-18 30 Y 20-22 30 Y 16-18 25 N 48 30 6-12 20-40 Y/N | (INCHES) (FEET) (Y/N) STRUCTURE 20-22 40 Y 4 16-18 30 Y 1 20-22 30 Y 3 16-18 25 N 1 48 30 1 6-12 20-40 Y/N 50 10 CY | |







| NAME OR | INITIALS AND DATE | GEOGRAPH | IIC INFORMATION |
|----------|-------------------|-----------|-----------------|
| DESIGNED | N. TRUSCOTT | LATITUDE | 47*29'33"N |
| CHECKED | W.J. SMITH | LONGITUDE | 120°25'15"W |
| DRAWN | G. MATSUMOTO | TN/SC/RG | T23N/S14/R19E |
| CHECKED | N. TRUSCOTT | DATE | MARCH 26, 2021 |
| | | | |


MONITOR SIDE CHANNEL RESTORATION

TYPE 4 ELJ


TYPE 4 ELJ DETAILS


16

SHEET 16 OF 22









TYPE 4 ELJ POST DIMENSIONING PLAN 1


SCALE: 1" = 5'

MONITOR SIDE CHANNEL RESTORATION

TYPE 4 ELJ LAYERING PLANS

18

SHEET 19 OF 22



THIS BAR DOES NOT MEASURE 1" THEN RAWING IS NOT PLOTTED TO ORIGINAL SCALE.



NAME OR INITIALS AND DATE GEOGRAPHIC INFORMATION N. TRUSCOTT 47°29'33"N ONGITUDE 120°25'15"W W.J. SMITH CHECKED G. MATSUMOTO N/SC/RG T23N/S14/R19E N. TRUSCOTT MARCH 26, 2021 CHECKED DATE

MONITOR SIDE CHANNEL RESTORATION

ELJ DETAILS 1

WILLOW TRENCH

19

DESIGN


FINAL

2021

26,

a

SHEET 19 OF 22







PROFILE

ABOVE ROOTWAD

CHANNEL SURFACE

ROOTWAD/ROOTWAD POST






NOTES

- 1. WRAP EACH BUNDLE WITH 1 INCH DIAMETER MANILA ROPE. TEST EACH COMPLETED BUNDLE TO ENSURE ALL INDIVIDUAL PIECES ARE SECURE FOR TRANSPORT.
- 2. MATERIAL FOR RACKING BUNDLE SHALL BE VARIABLE IN DIAMETER; LENGTHS SHALL BE 30 FT ± 1 FT.









AT LOCATION

PROFILES

EXCAVATION SPOILS TO BE PLACED AS


- CENTERLINE OF ROOTWAD


- EXCAVATION

BACKFILL AND COMPACTED WITH BUCKET

INDICATED ON ELJ

| NAM | E OR | INITIALS AND DATE | GEOGRAPH | IC INFORMATION |
|------|------|-------------------|-----------|----------------|
| DESI | SNED | N. TRUSCOTT | LATITUDE | 47*29'33"N |
| CHEC | KED | W.J. SMITH | LONGITUDE | 120°25'15"W |
| DRAV | 'N | G. MATSUMOTO | TN/SC/RG | T23N/S14/R19E |
| CHEC | KED | N. TRUSCOTT | DATE | MARCH 26, 2021 |
| | | | 1 | |






NOTES FOR TEMPORARY CLEARED ACCESS

- 1. TEMPORARY ACCESS ROUTES TO BE ROUTED TO MINIMIZE VEGETATION DISTURBANCE AND
- 2. CONTRACTOR SHALL STAKE PROPOSED ROUTES PRIOR TO ESTABLISHMENT. CLEARING LIMITS TO BE APPROVED BY CONTRACTING OFFICER PRIOR TO ANY CLEARING ACTIVITIES.
- 3. ACCESS SHALL BE MAINTAINED BY MINOR GRADING AND IMPORTATION OF BARK OR WOOD CHIP MULCH.
- 4. ALL TEMPORARY ACCESS ROUTES OUTSIDE OF PREVIOUSLY ESTABLISHED ACCESS ROADS SHALL BE DECOMPACTED TO A MINIMUM DEPTH OF SIX INCHES.







- 1. CONTRACTOR TO DESIGN TEMPORARY BRIDGE.
- 2. END OF BRIDGE SHALL BEAR ON HIGH BANKS WITH SUFFICIENT BEARING CAPACITY TO PREVENT SLOUGHING OR COLLAPSE OF SIDE CHANNEL BANKS.
- 3. CONCRETE ECOLOGY BLOCKS OR WOOD ABUTMENTS MAY BE USED TO SUPPORT ENDS OF TEMPORARY BRIDGE AS
- BRIDGES MAY BE CONSTRUCTED FROM LOGS, RAIL CAR BEDS OR APPROVED EQUAL AND DECKED WITH STEEL SHEET, WOOD LAGGING OR APPROVED EQUAL.






















RESTORATION

SANDBAG COFFERDAM









NAME OR INITIALS AND DATE GEOGRAPHIC INFORMATION W.J. SMITH ONGITUDE 120°25'15"W CHECKED G. MATSUMOTO N/SC/RG T23N/S14/R19E N. TRUSCOTT MARCH 26, 2021 CHECKED

MONITOR SIDE CHANNEL

SITE ACCESS AND DEWATERING **DETAILS**

SHEET **22** OF **22**