



March 14<sup>th</sup>, 2022

CHELAN COUNTY NATURAL RESOURCE DEPARTMENT  
CHUMSTICK CREEK-MOTTELER DRIVE CULVERT REPLACEMENT

**ADDENDUM NO. 1**

To the Contractors, Subcontractors, Planholders and Suppliers:

The following items contain additions, deletions, or modifications to the Plans and/or Specifications. This Addendum forms as a part of the Contract Documents. All updated contract Documents can be found at <https://www.co.chelan.wa.us/natural-resources/pages/current-opportunities>.

Bidders must acknowledge receipt of this Addendum on the Bid Proposal Declaration within the Bid Package.

**BID SUBMITTAL PACKAGE**

**1. Invitation to bid**

**1.1.** Estimated Range of Probable Cost in the last sentence of the third paragraph has changed to \$320,000-\$354,000 without WSST.

**2. Bid Proposal Form**

**2.1.** "RIPRAP" has been removed from the bid form in its entirety and bid items 10-14 have been updated accordingly.

**FINAL PLANS**

**3. Revised Final Plans Set**

**3.1.** Wingwall height has been increased, excavation and disposal has increased to 776 C.Y and all riprap has been removed from the Final Plans.

**SPECIAL PROVISIONS**

**4. Section 1-04 DEFINITIONS AND TERMS**

**4.1.** General Description is replaced with the following:

This contract provides for the removal of one, 11-foot-span by 7-foot-rise, CMP arch culvert and all associated fill and the installation of one, 24-foot-span by 12-foot-rise, inverted three-sided concrete box culvert. The work includes, but is not limited to: procurement of all associated materials; temporary traffic control and management; establishment and improvements of access routes and staging areas; in-water site isolation, control of in-water turbidity; bank excavation and restoration; stream channel excavation and restoration; road improvements and paving, and other work, all in accordance with the attached Contract Plans, these Contract Provisions, and the Standard Specifications.

**5. Section 2-09.3(1) Disposal of Excavated Materials**

**5.1.** The last sentence of this section is replaced with “Excavated fill material is estimated at 776 C.Y.”

**6. Section 6-20 BURIED STRUCTURES**

**6.1.** All mention of Riprap has been removed from subsections 6-20.1, 6-20.2, 6-20.3, 6-20.4 and 6-20.5.

END OF ADDENDUM NO. 1

---