

**Motteler Drive Culvert Replacement
Bidder Questions and Clarifications**

Question	Response	Date
Is there a Geotechnical Report for the site?	section 1-02.4(2) Subsurface Information: A geotechnical investigation was complete by Aspect Consulting and can be made available upon request.	3/10/2022
Is there a load rating on the downstream bridge?	HL-93/U80	3/18/2022
Is there any work to be done on the downstream concrete retaining wall on left bank?	Only to the extent necessary to install the new structure as shown on the plans.	3/18/2022
Is there a size requirement for the pedestrian bridge?	Sheet 4 of the Designs denotes a 6' wide pedestrian crossing.	3/18/2022
Since this is a Public Works crossing, are steel guardrails required?	Per the Designs and Special Provisions, an 18" traffic curb and object markers on all four corners is required.	3/18/2022
Are there any buried utilities?	Not that we are aware of, however per section 1-07.17 of the special provisions, the Contractor is responsible for locating and protecting all utilities during construction.	3/18/2022
On the plans it says .25 HMA but in the Specials it talks about BST?	It is HMA per the plans. Addendum 2 reflects these corrections to the special provisions.	3/21/2022
Can you explain the discrepancy between the streambed sediment sizes shown on the plans versus that referenced in the specs?	Per the engineer "the specifications reference a material type, but there is a note in the specs saying actual sizes per plans. The material on the plans needs to be provided to the approximate sizes shown."	3/22/2022