
NASON CREEK KAHLER REACH HABITAT IMPROVEMENT PROJECT

CHELAN COUNTY NATURAL RESOURCE DEPARTMENT



DRAWING LIST				
SHEET NUMBER	SHEET TITLE			
1	COVER SHEET			
2	GENERAL NOTES			
3	LEGEND			
4	EXISTING CONDITIONS PLAN			
5	PROPOSED CONDITIONS OVERVIEW PLAN			
6	ACCESS AND STAGING PLAN			
7	PROPOSED CONDITIONS - SITE 1			
8	CONSTRUCTION SEQUENCING - SITE 1			
9	SEEDING PLAN - SITE 1			
10	PROPOSED CONDITIONS - SITE 2			
11	CONSTRUCTION SEQUENCING - SITE 2			
12	SEEDING PLAN - SITE 2			
13	TYPE 1 ELJ DETAILS			
14	TYPE 1 ELJ LAYERING PLANS - 1			
15	TYPE 1 ELJ LAYERING PLANS — 2			
16	TYPE 2 ELJ DETAILS			
17	TYPE 2 ELJ LAYERING PLANS - 1			
18	TYPE 2 ELJ POST DIMENSIONING PLAN			
19	SIDE CHANNEL CONNECTION GRADING			
20	ROAD IMPROVEMENTS			
21	RESTORATION DETAILS			
22	TESC DETAILS			
23	SEED SCHEDULES			





CONTACT INFORMATION


OWNER: CHELAN COUNTY NATURAL RESOURCE DEPARTMENT

411 WASHINGTON STREET, SUITE 201 WENATCHEE, WA 98801 PHONE: (509) 667-6533

ENGINEER: NATURAL SYSTEMS DESIGN, INC

1900 N NORTHLAKE WAY, SUITE 211 SEATTLE, WA 98103 (206) 834-0175









NAME OR I	NITIALS AND DATE	GEOGRAPH	IC INFORMATION
DESIGNED	JMS, ELD	LATITUDE	N047* 46' 7.64"
CHECKED	TBA	LONGITUDE	W120* 46' 7.76"
DRAWN	JGJ	TN/SC/RG	T26N/S7/R17E
CHECKED	JWS, GM	DATE	

SHEET 1 OF 23

- 2. NATURAL SYSTEMS DESIGN, HEREAFTER REFERRED TO AS "ENGINEER", IS RESPONSIBLE FOR THE PREPARATION OF THESE ORIGINAL PLANS AND ASSOCIATED SPECIFICATIONS; AND WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGE, OR USE, OF THESE PLANS WHICH INCLUDES ALTERATION, DELETION, OR EDITING OF THIS DOCUMENT WITHOUT EXPLICIT WRITTEN PERMISSION FROM THE ENGINEER. ANY OTHER UNAUTHORIZED USE OF THIS DOCUMENT IS PROHIBITED.
- 3. MINOR MODIFICATIONS ARE EXPECTED TO SUIT JOB SITE DIMENSIONS OR CONDITIONS. SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. THE OWNER, ENGINEER AND APPROPRIATE REGULATORY AGENCIES SHALL BE NOTIFIED OF ANY OWNER-AUTHORIZED CHANGE RESULTING IN MORE THAN A 10% DESIGN CHANGE OF PROPOSED FOOTPRINT OR THAT SIGNIFICANTLY AFFECTS THE INTENDED BENEFIT OR FUNCTION OF A PROJECT ELEMENT.
- 4. THE LOCATION OF ALL FEATURES SHOWN IS APPROXIMATE.
- THE CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; AND FURTHER AGREES THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS IN ACCORDANCE WITH THE PROVISIONS OUTLINED BY THE PROJECT CONTRACT AND SPECIFICATIONS.
- 6. ALL IMPROVEMENTS SHALL BE ACCOMPLISHED UNDER THE APPROVAL, INSPECTION, AND TO THE SATISFACTION OF THE OWNER. IMPROVEMENT CONSTRUCTION SHALL COMPLY WITH THESE PLANS AND THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT) STANDARD PLANS FOR CONSTRUCTION OF ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION, CURRENT EDITION UNLESS NOTED OTHERWISE. ALL REFERENCES TO THE "STANDARD SPECIFICATIONS" SHALL MEAN THE WASHINGTON STATE STATE DEPARTMENT OF TRANSPORTATION (WSDOT) STANDARD SPECIFICATIONS FOR CONSTRUCTION OF LOCAL STREETS AND ROADS, CURRENT EDITION. CONSTRUCTION NOT SPECIFIED ON THESE PLANS SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS. THE CONTRACTOR IS OBLIGATED TO BE FAMILIAR WITH APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS NOT DISCUSSED IN THE GENERAL NOTES. THE CONTRACT SPECIAL PROVISIONS SHALL SUPERSEDE THOSE OF THE STANDARD SPECIFICATIONS WHERE DISCREPANCIES OCCUR.
- 7. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND SUBCONTRACTOR(S) TO EXAMINE THE PROJECT SITE PRIOR TO THE OPENING OF BID PROPOSALS. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED, SUCH AS THE NATURE AND LOCATION OF THE WORK; AND THE GENERAL AND LOCAL CONDITIONS, PARTICULARLY THOSE AFFECTING THE AVAILABILITY OF TRANSPORTATION, THE DISPOSAL HANDLING, AND STORAGE OF MATERIALS, AVAILABILITY OF LABOR, WATER, ELECTRICITY, ROADS, THE UNCERTAINTIES OF WEATHER. THE CONDITIONS OF THE GROUND, SURFACE AND SUBSURFACE MATERIALS, GROUNDWATER, THE EQUIPMENT AND FACILITIES NEEDED FOR AND DURING THE PERFORMANCE OF THE WORK, AND THE COSTS THEREOF. ANY FAILURE BY THE CONTRACTOR AND SUBCONTRACTOR(S) TO ACQUAINT THEMSELVES WITH ALL THE AVAILABLE INFORMATION WILL NOT RELIEVE THE CONTRACTOR AND SUBCONTRACTOR(S) FROM RESPONSIBILITY FOR PROPERLY ESTIMATING THE DIFFICULTY AND COST OF SUCCESSFULLY PERFORMING THE WORK.
- 8. THE CONTRACTOR IS RESPONSIBLE FOR REVIEWING THE CONTRACT DOCUMENTS AND FOR ALL SUBMITTALS REQUIRED TO THE OWNER FOR REVIEW AND ACCEPTANCE.

PERMIT NOTES

- 1. EVERY REASONABLE EFFORT SHALL BE MADE TO CONDUCT THE ACTIVITIES SHOWN IN THESE PLANS, IN A MANNER THAT MINIMIZES THE ADVERSE IMPACT ON WATER QUALITY, FISH AND WILDLIFE, AND THE NATURAL ENVIRONMENT.
- 2. ALL WORK WILL BE IN COMPLIANCE WITH PERMIT CONDITIONS ISSUED BY PERTINENT REGULATORY AGENCIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE COPIES OF ALL PERMITS ON THE JOB SITE, UNDERSTAND AND COMPLY WITH ALL PERMIT CONDITIONS.
- 3. ALL WORK THAT DISTURBS THE SUBSTRATE, BANK, OR SHORE OF A WATERS OF THE STATE THAT CONTAINS FISH LIFE SHALL BE CONDUCTED ONLY DURING THE WORK PERIOD FOR THAT WATERBODY AS ALLOWED BY RELEVANT HYDRAULIC WORK PERMITS. THOSE PORTIONS OF THE PROJECT WORK THAT OCCUR OUTSIDE OR ABOVE THE ORDINARY HIGH WATER MARK (ABOVE THE USACE JURISDICTIONAL LINE) ARE NOT SUBJECT TO THE WORK PERIODS DESCRIBED ABOVE UNLESS SPECIFIED IN THE RELEVANT PERMITS
- 4. ALL ACTIVITIES THAT INVOLVE WORK ADJACENT TO, OR WITHIN THE WETTED CHANNEL SHALL, AT ALL TIMES, REMAIN CONSISTENT WITH ALL APPLICABLE WATER QUALITY STANDARDS: EFFLUENT LIMITATION; AND STANDARDS OF PERFORMANCE, PROHIBITIONS, PRETREATMENT STANDARDS, AND MANAGEMENT PRACTICES ESTABLISHED PURSUANT TO THE CLEAN WATER ACT OR PURSUANT TO APPLICABLE STATE AND LOCAL LAW.

THIS BAR DOES NOT

MEASURE 1" THEN RAWING IS NOT PLOTTED

TO ORIGINAL SCALE.

- 5. IF AT ANY TIME, AS A RESULT OF PROJECT ACTIVITIES, FISH ARE OBSERVED IN DISTRESS, A FISH KILL OCCURS, OR WATER QUALITY PROBLEMS DEVELOP (INCLUDING EQUIPMENT LEAKS OR SPILLS), OPERATIONS SHALL CEASE AND THE OWNER SHALL BE NOTIFIED IMMEDIATELY.
- 6. IF, DURING CONSTRUCTION, ARCHAEOLOGICAL REMAINS ARE ENCOUNTERED, CONSTRUCTION IN THE VICINITY SHALL BE HALTED, AND THE STATE OFFICE OF HISTORIC PRESERVATION AND THE OWNER SHALL BE NOTIFIED IMMEDIATELY.

SURVEY NOTES

- 1. UNLESS NOTED OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SURVEY MONUMENTS AND OTHER SURVEY MARKERS
- 2. THE CONTRACTOR SHALL MAINTAIN A SET OF PLANS ON THE JOB SHOWING "AS-CONSTRUCTED" CHANGES MADE TO DATE. UPON COMPLETION OF THE PROJECT, THE CONTRACTOR SHALL SUPPLY TO OWNER A SET OF PLANS, MARKED UP TO THE SATISFACTION OF THE OWNER, REFLECTING THE AS-CONSTRUCTED MODIFICATIONS.
- 3. ELEVATIONS SHOWN ON THE PLANS FOR PIPE INVERTS, TOPS OF BANKS, THALWEG, GRADE CONTROLS, ETC., ARE BASED UPON THE TOPOGRAPHIC INFORMATION SHOWN ON THE PLANS. THE CONTRACTOR SHALL VERIFY ALL NECESSARY SURFACE ELEVATIONS IN THE FIELD AND NOTIFY THE OWNER OF ANY DISCREPANCIES, WHICH MIGHT AFFECT PROPER OPERATION OF THE NEW FACILITIES BEFORE BREAKING GROUND AND PRIOR TO FACILITY INSTALLATION. THE OWNER SHALL BE CONTACTED IN THE EVENT ELEVATIONS ARE INCORRECT SO THAT THE PROPER ADJUSTMENTS CAN BE MADE BY ENGINEER PRIOR TO THE INSTALLATION OF THE FACILITIES. AS SET FORTH IN THE SPECIAL PROVISIONS.
- 4. LIDAR FOR THIS PROJECT WAS PROVIDED BY PSLC AND IS REPRESENTATIVE OF 2015 CONDITIONS. ADDITIONAL TOPOGRAPHIC DATA WAS COLLECTED BY NSD IN 2015. THE VERTICAL DATUM IS NAVD88 (FT). THE HORIZONTAL DATUM IS NAD83 WASHINGTON STATE PLANE NORTH (US SURVEY FT).

EROSION, SEDIMENT CONTROL AND WATER MANAGEMENT NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING ALL TEMPORARY EROSION CONTROL MEASURES. THE EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND PERFORMANCE OF THE TEMPORARY EROSION CONTROL MEASURES THROUGHOUT THE DURATION OF THE PROJECT.
- 2. A SEDIMENT AND EROSION CONTROL PLAN WILL BE DEVELOPED BY THE CONTRACTOR AND SUBMITTED FOR APPROVAL BY OWNER AND/OR THE ENGINEER BEFORE ANY CONSTRUCTION MAY BEGIN. THE SEDIMENT AND EROSION CONTROL PLAN WILL IDENTIFY BEST MANAGEMENT PRACTICES TO ENSURE THAT THE TRANSPORT OF SEDIMENT TO SURFACE WATERS, DRAINAGE SYSTEMS, AND ADJACENT PROPERTIES IS MINIMIZED.
- 3. ACTIVITIES SHALL BE DESIGNED AND CONSTRUCTED TO AVOID AND MINIMIZE ADVERSE IMPACTS TO WATERS OF THE UNITED STATES TO THE MAXIMUM EXTENT PRACTICAL THROUGH THE USE OF PRACTICAL ALTERNATIVES. ALTERNATIVES THAT SHALL BE CONSIDERED INCLUDE THOSE THAT MINIMIZE THE NUMBER AND EXTENT OF IN-WATER WORK AND EQUIPMENT CROSSINGS OF WETTED CHANNELS.
- 4. AT NO TIME SHALL SEDIMENT-LADEN WATER BE DISCHARGED OR PUMPED DIRECTLY INTO THE SUBJECT RIVER, STREAM, OR WETLAND. WATER SHALL BE DISCHARGED IN ACCORDANCE WITH REQUIREMENTS SET FORTH IN THE PROJECT PERMITS AND / OR SPECIFICATIONS.
- 5. IF HIGH WATER LEVEL CONDITIONS THAT CAUSE SILTATION OR EROSION ARE ENCOUNTERED DURING CONSTRUCTION WORK SHALL STOP UNTIL THE WATER LEVEL SUBSIDES
- 6. PERMIT CONDITIONS CONTAIN SPECIFIC REQUIREMENTS FOR THE CONTROL OF EROSION AND TURBIDITY FROM PROJECT OPERATIONS. TURBIDITY WILL BE MONITORED ON A FREQUENT BASIS BY THE PROJECT MANAGEMENT AND INSPECTION STAFF ON-SITE. TURBIDITY AMOUNTS IN EXCESS OF THE PERMITTED CONCENTRATIONS AND/OR DURATIONS WILL CAUSE WORK TO BE STOPPED UNTIL IMPROVED PRACTICES ARE IN EFFECT AND THE PROBLEMS CONTROLLED. THE CONTRACTOR IS COMPLETELY RESPONSIBLE FOR ANY PROJECT DELAYS THAT OCCUR BY NATURE OF THIS FAILURE TO ADEQUATELY CONTAIN SEDIMENT ON-SITE.
- 7. CONTRACTOR SHALL LIMIT MACHINERY MOVEMENT TO CONSTRUCTION AREAS DEFINED ON SITE PLAN OR IDENTIFIED AS ACCEPTABLE BY THE ENGINEER OR OWNER.
- 8. ALL EXTERNAL GREASE AND OIL SHALL BE PRESSURE-WASHED OFF THE EQUIPMENT PRIOR TO TRANSPORT TO THE SITE.
- 9. ALL EQUIPMENT OPERATING BELOW OHWM SHALL UTILIZE READILY BIODEGRADABLE VEGETABLE-BASED HYDRAULIC FLUIDS.
- 10. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT NO PETROLEUM PRODUCTS, HYDRAULIC FLUID, SEDIMENTS, SEDIMENT-LADEN WATER, CHEMICALS, OR ANY OTHER TOXIC OR DELETERIOUS MATERIALS ARE ALLOWED TO ENTER OR LEACH INTO THE SUBJECT RIVER, STREAM OR WETLAND
- 11. THE CONTRACTOR SHALL HAVE AN EMERGENCY SPILL KIT ONSITE AT ALL TIMES.

- 12. NO TREES OR WETLAND VEGETATION SHALL BE REMOVED UNLESS THEY ARE SHOWN AND NOTED TO BE REMOVED ON THE PLANS OR AS DIRECTLY SPECIFIED ON-SITE BY THE OWNER OR ENGINEER. ALL TREES CONFLICTING WITH GRADING SHALL BE REMOVED. NO GRADING SHALL TAKE PLACE WITHIN THE DRIP LINE OF TREES NOT TO BE REMOVED UNLESS OTHERWISE APPROVED.
- 13. FOLLOWING CONSTRUCTION, SITE RESTORATION WILL INCLUDE ESTABLISHING LONG-TERM EROSION PROTECTION MEASURES. THESE MEASURES WILL INCLUDE PLANTINGS, EROSION CONTROL FABRIC, SEED, AND MULCH. EQUIPMENT AND EXCESS SUPPLIES WILL BE REMOVED AND THE WORK AREA WILL BE CLEANED. MAINTENANCE ACTIVITIES FOR THE NEWLY CONSTRUCTED RESTORATION PROJECTS ARE ANTICIPATED TO OCCUR PERIODICALLY.

CONSTRUCTION NOTES

- 1. CONTRACT DOCUMENTS REFER TO THESE PLANS.
- 2. CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, AND LABOR NECESSARY TO COMPLETE ALL WORK AS INDICATED IN THE CONTRACT DOCUMENTS.
- CONSTRUCTION HOURS SHALL BE WEEKDAYS BETWEEN 7:00 A.M. AND 6:30 P.M. UNLESS PRIOR APPROVAL IS RECEIVED FROM THE OWNER.
- ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE OWNER PRIOR TO PROCEEDING WITH THE WORK.
- 5. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY INDICATED OTHERWISE BY THE OWNER OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE
- 6. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES.
- 7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING THE BEST SKILLS AND ATTENTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT.
- 8. THE CONTRACTOR SHALL MAKE ALL NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, ROADWAY, DRAINAGE WAYS, PRIVATE BRIDGE, CULVERTS, AND VEGETATION UNTIL SUCH ITEMS ARE TO BE DISTURBED OR REMOVED AS INDICATED ON THE CONTRACT
- THE CONTRACTOR SHALL KEEP THE JOB SITE CLEAN AND HAZARD FREE. CONTRACTOR SHALL DISPOSE OF ALL DIRT, DEBRIS, AND RUBBISH FOR THE DURATION OF THE WORK. UPON COMPLETION OF WORK, CONTRACTOR SHALL REMOVE ALL MATERIAL AND EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY.
- 10. NOTES AND DETAILS ON THE PLANS SHALL TAKE PRECEDENCE OVER GENERAL NOTES HEREIN.
- 11. DIMENSIONS CALLOUTS SHALL TAKE PRECEDENCE OVER SCALES SHOWN ON THE PLANS.
- 12. THE PLANS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF ALL CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURES, WORKS, AND THE PUBLIC DURING CONSTRUCTION.
- 13. MATERIAL SHALL NOT BE STORED OUTSIDE OF IDENTIFIED STAGING AREAS. THE CONTRACTOR SHALL USE ONLY DESIGNATED SPECIFIC SITES FOR STORAGE OF EQUIPMENT AND MATERIALS AS SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SECURITY OF ALL FOLIPMENT AND MATERIALS









NAME OR INITIALS AND DATE GEOGRAPHIC INFORMATION TITUDE N047' 46' 7.64" TBA ONGITUDE W120* 46' 7.76" N/SC/RG <u>T26N/S7/R17E</u> JGJ JWS, GM DATE

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT PROJECT

GENERAL NOTES

SHEET 2 OF 23

ပ္မ



- ଉପ୍ତର୍ବର୍ବର୍ବର୍ବର୍ବର୍ବର୍ବର୍












2021 100% PLANS - FOR CONSTRUCTION


20,


Dec





























TYPE 1 ELJ SECTION (LOOKING DOWNSTREAM)


10' 5' 0 10' 20' SCALE: 1"=10'-0"

NOTES

. ALL STRUCTURE LOCATIONS AND POST BOTTOM ELEVATIONS SHALL BE STAKED BY THE ENGINEER PRIOR TO EXCAVATION, ASSEMBLY AND INSTALLATION OF EACH STRUCTURE.

SCALE: 1"=10'


- 2. CONTRACTOR SHALL EXCAVATE TO THE STRUCTURE BOTTOM ELEVATION AND MAINTAIN A DEWATERED WORK AREA SO LAYERING AND CONNECTIONS CAN BE MADE PER LAYERING SHEETS.
- 3. EXCAVATION SPOILS SHALL BE STAGED ACCORDING TO THE PERMIT REQUIREMENTS.
- 4. THE WOOD LAYER PLACEMENT IN EACH LOGJAM LAYER SHALL BE FIELD VERIFIED BY ENGINEER OR OWNER REPRESENTATIVE PRIOR TO
- 5. THE FINISHED ELEVATION AND WIDTH OF ANY ELJ SHALL NOT EXCEED THE DIMENSIONS SHOWN IN THESE PLANS.
- BACKFILL EXTENTS MAY VARY AND ARE TO BE CONSTRUCTED WITH NATIVE ALLUVIUM FROM EXCAVATION SPOILS. BACKFILL ELEVATION IS NOT TO EXCEED THE SPECIFIED GRADE.
- 7. THE CONTRACTOR SHALL CLEARLY MARK EACH LOG WITH A UNIQUE COLOR IDENTIFYING THE LOG TYPE FOR VERIFICATION BY THE CONTRACT OFFICER BEFORE PLACEMENT INTO STRUCTURES.
- 8. FOR ROOTWAD POST SIZE DIMENSION SPECIFICATIONS, SEE $\begin{pmatrix} 4 \\ 21 \end{pmatrix}$
- BOULDERS >24" EXCAVATED OUT DURING POST INSTALLATION ARE TO BE STOCKPILED SEPARATELY AND INCORPORATED INTO BACKFILL, OR PLACED IN THE STREAM CHANNEL WITHIN 10 FT OF THE ELJ, AS DIRECTED BY THE ENGINEER.



TYPE 1 ELJ PERSPECTIVE VIEW NOT TO SCALE

TYPE 1 ELJ MATERIALS SCHEDULE						
LOG ID	DIA (INCHES)	LENGTH (FEET)	ROOTWAD (Y/N)	QUANTITY PER STRUCTURE	NOTES	
RPD-25	20 MIN	25	Y	9	MUST BE DOUGLAS FIR	
RD-4	20	40	Y	3		
RB-4	24	40	Y	2		
B-4	24	40	N	1		
D-4	20	40	N	4		
RACKING	6-12	30-40	Y/N	100		
SLASH	<3	<4	N	100 CY		







SCALE: 1"=10"



SCALE: 1"=10'-0'


NAME OR	INITIALS AND DAT	E	GEOGRAPH	IIC INFORMATION
DESIGNED	JMS, ELD		LATITUDE	N047* 46' 7.64"
CHECKED	TBA		LONGITUDE	W120° 46' 7.76"
DRAWN	JGJ		TN/SC/RG	T26N/S7/R17E
CHECKED	JWS, GM		DATE	


NASON CREEK KAHLER REACH HABITAT IMPROVEMENT PROJECT

TYPE 1 ELJ DETAILS


13

SHEET 13 OF 23





LAYER 4 LAYER 5




SECTION VIEWS

CY) INTO BACKFILL.

2. SAWCUT POST TOPS. $\left(\frac{3}{21}\right)$

1. BACKFILL BANK TO PRE-PROJECT GRADE. INCORPORATE SLASH (~30





TYPE 1 POST LAYOUT PLAN

SCALE: 1" = 5'




NOTES

1. THE ENGINEER WILL STAKE THE STAKEOUT POINT LOCATIONS SHOWN. THE CONTRACTOR SHALL MAINTAIN STAKES OR REFERENCE LINE TO STAKES FOR ACCURATE POST PLACEMENT DURING CONSTRUCTION.



2. BOLT LOGS TO POSTS AT 4 LOCATIONS

1. PLACE 2 LOGS





NAME OR I	NITIALS AND	DATE	GEOGF	RAPHIC INFORMATION
DESIGNED	JMS, ELD		LATITUD	E N047* 46' 7.64"
CHECKED	TBA		LONGITU	JDE W120* 46' 7.76"
DRAWN	JGJ		TN/SC/	/RG T26N/S7/R17E
CHECKED	JWS, GM		DATE	=

-12" LIFT OF SLASH IN BACKFILL AND OVER TOP OF STRUCTURE.


SPREAD ANY EXCESS ON FINISHED SURFACE

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT **PROJECT**

TYPE 1 ELJ LAYERING PLANS - 2

15


SHEET 15 OF 23



20 TYPE 2 ELJ PLAN SCALE: 1"=10' SCALE: 1"=10'-0"

NOTES

- 1. ALL STRUCTURE LOCATIONS AND POST BOTTOM ELEVATIONS SHALL BE STAKED BY THE ENGINEER PRIOR TO EXCAVATION, ASSEMBLY AND INSTALLATION OF EACH STRUCTURE
- 2. WHEN STRUCTURES ABUT BANKS, EXCAVATE A PORTION OF THE BANK AS NEEDED TO INSTALL THE STRUCTURE. REGRADE THE BANK FOLLOWING COMPLETION AND PLACE EXCESS MATERIAL IN LEE OF ELJ AS DRAWN. THE SIDE OF THE STRUCTURE WHICH THE BANK IS ALIGNED WITH WILL VARY.
- 3. CONTRACTOR SHALL EXCAVATE TO THE STRUCTURE BOTTOM ELEVATION AND MAINTAIN A DEWATERED WORK AREA SO LAYERING AND CONNECTIONS CAN BE MADE PER LAYERING SHEETS.
- 4. EXCAVATION SPOILS SHALL BE STAGED ACCORDING TO THE PERMIT
- 5. THE WOOD LAYER PLACEMENT IN EACH LOGJAM LAYER SHALL BE FIELD VERIFIED BY ENGINEER OR OWNER REPRESENTATIVE PRIOR TO
- 6. THE FINISHED ELEVATION AND WIDTH OF ANY ELJ SHALL NOT EXCEED THE DIMENSIONS SHOWN IN THESE PLANS.
- BACKFILL EXTENTS MAY VARY AND ARE TO BE CONSTRUCTED WITH NATIVE ALLUVIUM FROM EXCAVATION SPOILS. BACKFILL ELEVATION IS NOT TO EXCEED THE SPECIFIED GRADE.
- 8. THE CONTRACTOR SHALL CLEARLY MARK EACH LOG WITH A UNIQUE COLOR IDENTIFYING THE LOG TYPE FOR VERIFICATION BY THE CONTRACT OFFICER BEFORE PLACEMENT INTO STRUCTURES.
- 9. FOR ROOTWAD POST SIZE DIMENSION SPECIFICATIONS, SEE
- 10. BOULDERS >24" EXCAVATED OUT DURING POST INSTALLATION ARE TO BE STOCKPILED SEPARATELY AND INCORPORATED INTO BACKFILL, OR PLACED IN THE STREAM CHANNEL WITHIN 10 FT OF THE ELJ, AS DIRECTED BY THE ENGINEER.



TYPE 2 ELJ MATERIALS SCHEDULE							
LOG ID	DIA (INCHES)	LENGTH (FEET)	ROOTWAD (Y/N)	QUANTITY PER STRUCTURE	NOTES		
RPD-25	20 MIN	25	Y	7	MUST BE DOUGLAS FIR		
RB-4	24	40	Y	1			
RD-3	20	30	Υ	2			
D-3	20	30	N	1			
RACKING	6-12	20-30	Y/N	50			
SLASH	<3	<4	N	30 CY			











cian	NAME OR I	NITIALS AND DATE	GEOGRAPH	IC INFORMATION
:Didit	DESIGNED	JMS, ELD	LATITUDE	N047* 46' 7.64"
	CHECKED	TBA	LONGITUDE	W120* 46' 7.76"
	DRAWN	JGJ	TN/SC/RG	T26N/S7/R17E
	CHECKED	JWS, GM	DATE	

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT **PROJECT**

SCALE: 1"=10"

TYPE 2 ELJ DETAILS

16

- FOR CONSTRUCTION

100% PLANS


2021


20,

Dec

SCALE: 1"=10'-0

SHEET 16 OF 23






TYPE 2 ELJ POST LAYOUT PLAN SCALE: 1" = 5'



<u>NOTES</u>

- THE ENGINEER WILL STAKE THE STAKEOUT POINT LOCATIONS SHOWN. THE CONTRACTOR SHALL MAINTAIN STAKES OR REFERENCE LINE TO STAKES FOR ACCURATE POST PLACEMENT DURING CONSTRUCTION.
- 2. THE ORDER OF POST INSTALLATION SHOWN ON SHEET 17 IS APPROXIMATE. THE CONTRACTOR SHALL DETERMINE THE ORDER OF INSTALLATION SEQUENCE.



IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT PLOTTED TO ORIGINAL SCALE.




NAME OR	INITIALS AND	DATE	GEOGRAPH	IC INFORMATION
DESIGNED	JMS, ELD		LATITUDE	N047* 46' 7.64"
CHECKED	TBA		LONGITUDE	W120* 46' 7.76"
DRAWN	JGJ		TN/SC/RG	T26N/S7/R17E
CHECKED	JWS. GM		DATE	_
CHLCKED			Ditte	


NASON CREEK KAHLER REACH HABITAT IMPROVEMENT PROJECT

TYPE 2 ELJ POST DIMENSIONING PLAN

18

SHEET 18 OF 23






SECTION B-B'
SCALE: H: 1' = 5', V: 1" = 5'

SIDE CHANNEL CONNECTION PLAN

SCALE: 1" = 10'

<u>NOTES</u>


- EXCAVATE ACCESS ROAD BETWEEN EXISTING SIDE CHANNEL 1 WETLAND SWALE AND NASON CREEK. HAUL EXCAVATED MATERIAL AND SPREAD AT THE ON-SITE DISPOSAL LOCATION SHOWN ON THE PLANS OR AS DIRECTED BY CONTRACT OFFICER.
- MINIMIZE IMPACTS TO EXISTING TREES AND SHRUBS TO THE EXTENT POSSIBLE.
- PLACE CLEARED TREES AND SHRUBS AS SLASH MATERIAL IN ADJACENT TYPE 2 ELJ(S) AS DIRECTED BY THE ENGINEER.
- ISOLATE EARTHWORK FROM FLOWING WATERS. PUMP OUT SEDIMENT LADEN WATER TO UPLAND SITE PRIOR TO CONNECTION OF CHANNEL TO FLOWING WATERS.
- ESTIMATED CUT QUANTITY IS 250 CY.













tural Systems Design	NAME OR II	NITIALS AND DATE	GEOGRAPH	IC INFORMATION
tural systems Design	DESIGNED	JMS, ELD	LATITUDE	N047* 46' 7.64"
	CHECKED	TBA	LONGITUDE	W120° 46' 7.76"
	DRAWN	JGJ	TN/SC/RG	T26N/S7/R17E
	CHECKED	JWS, GM	DATE	


NASON CREEK KAHLER REACH HABITAT IMPROVEMENT **PROJECT**


SIDE CHANNEL CONNECTION **GRADING**

19

Dec

SHEET 19 OF 23






- 1. REMOVE BARK AT CONNECTION POINTS.
- 2. DRILL HOLE THROUGH CENTER OF LOGS.
- 3. TIGHTEN SUFFICIENTLY TO ELIMINATE GAP BETWEEN LOGS BUT NOT CRUSH BOLES. PEEN THREADS OR TACK WELD NUT TO ALL—THREAD
- 4. ALL-THREAD TO BE ASTM TYPE A 307, GRADE A. LENGTH VARIES BY CONNECTION.
- 5. MULTIPLE LOG CONNECTIONS AT SAME JOINT WILL USE SINGLE PIECE OF ALL—THREAD TO MINIMIZE HOLES IN POSTS.




ROOTWAD/ROOTWAD POST



ABBREVIATIONS:

B =BOLE (EG., STEM, TRUNK) OF TREE RW = ROOTWADDRW = DIAMETER OF ROOTWAD DBH = DIAMETER AT BREAST HEIGHT MEASURED WITH BARK OFF

ROOTWAD




DESIGN EMBEDMENT DEPTH SHALL BE MEASURED FROM THE BOTTOM OF THE BOLE WHERE THE ROOTFAN ROOTS ARE SPREAD TO THEIR MAXIMUM DIAMETER, ONLY ACCOUNTING FOR MAJOR ROOTS >3" IN DIAMETER AND DO NOT VARY MORE THAN 3" IN LENGTH BELOW THE BOTTOM OF THE BOLE.

CHECKED

JWS, GM


L DEPTH OF ROOT FAN $(TYP \sim 3-4 FT)$


ROOTWAD DIMENSIONING REQUIREMENTS



PROFILE

SAWCUT POST





BATTER POST INSTALLATION

AME OR INITIALS AND DATE GEOGRAPHIC INFORMATION N047' 46' 7.64" ONGITUDE <u>W120* 46' 7.76"</u>

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT **PROJECT**

RESTORATION DETAILS

21

SHEET 21 OF 23


- FOR CONSTRUCTION

100% PLANS


2021

20,


Dec








- WRAP "SUPER SACKS" WITH IMPERVIOUS PLASTIC LINER TO PREVENT SEEPAGE.
- 2. BACKFILL THE DOWNSTREAM SIDE COFFER DAM WITH NATIVE, ADJACENT ALLUVIUM.
- 3. USE "SUPER SACKS" AS BUTTRESSES AS REQUIRED.
- 4. ALTERNATIVE METHODS FOR COFFERDAM MUST COMPLY WITH ARBO REQUIREMENTS.



PROFILE VIEW






NOTES:

- 1. CONTRACTOR TO DESIGN TEMPORARY BRIDGE.
- BRIDGE SHALL BE LOCATED SUCH THAT ONLY ONE SPAN IS USED TO ELIMINATE IMPACTS TO SUBSTRATE OF CHANNEL.
- 3. END OF BRIDGE SHALL BEAR ON HIGH BANKS WITH SUFFICIENT BEARING CAPACITY TO PREVENT SLOUGHING OR COLLAPSE OF SIDE CHANNEL BANKS.
- 4. CONCRETE ECOLOGY BLOCKS OR WOOD ABUTMENTS MAY BE USED TO SUPPORT ENDS OF TEMPORARY BRIDGE AS NEEDED.
- 5. BRIDGES MAY BE CONSTRUCTED FROM LOGS OR APPROVED EQUAL AND DECKED WITH STEEL SHEET, WOOD LAGGING OR APPROVED EQUAL.






REFERENCE; WASHINGTON STATE DEPARTMENT OF ECOLOGY STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON (FIGURE 4-2)

STABILIZED CONSTRUCTION ENTRANCE


















NAME OR IN	ITIALS AND DAT	ΓE (GEOGRAPHI	C INFORMATION
DESIGNED _	MS, ELD		LATITUDE	N047* 46' 7.64"
CHECKED 1	BA		LONGITUDE	W120* 46' 7.76"
DRAWN _	IGJ		TN/SC/RG	T26N/S7/R17E
CHECKED _	IWS, GM		DATE	

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT PROJECT

TESC DETAILS

22

SHEET 22 OF 23



PLANT COMMUNITY	SPECIES	COMMON NAME	LBS PLS/ACRE
UPLAND SEED MIX	Achillea millefolium	Western Yarrow	0.5
	Achnatherum hymenoides	Indian Ricegrass	6
	Agropyron spicatum	Bluebunch Wheatgrass	6
	Bromus carinatus	Mountain Brome	0.5
	Elymus glaucus	Wild Rye	0.5
	Festuca idahoensis Idaho Fesci		3
	Linum lewisii	Prairie Flax	0.25
	Lomatium dissectum	Desert Parsley	1
	Lomatium nudicaule	Barestem Biscuitroot	1
	Lupinus sericeus	Silky Lupine	0.25
	Triticum aestivum x secale cereale	Sterile Triticale	20
	Poa secunda	Sandberg Bluegrass	6

SEED MIX QUANTITIES					
MIX	SITE 1 QTY (AC)	SITE 2 QTY (AC)	ROAD IMPROVEMENTS AREA QTY (AC)		
UPLAND	2.5	0.6	0.1		
FLOODPLAIN	0.9	0.8			





PLANT COMMUNITY	SPECIES	COMMON NAME	LBS PLS/ACRE
FLOODPLAIN SEED MIX	Agrostis scabra	Hair Bentgrass	0.5
	Deschampsia cespitosa	Tufted Hairgrass	1
	Erigeron speciosus	Aspen Fleabane	0.75
	Festuca rubra var. rubra	Red Fescue	2
	Juncus tenus	Slender Rush	0.5
	Triticum aestivum x secale cereale	Sterile Triticale	20

SEEDING NOTES

- 1. FOLLOWING CONSTRUCTION, ALL AREAS ABOVE ORDINARY HIGH WATER MARK DISTURBED DUE TO EARTHWORK, CLEARING, ACCESS, STAGING OR OTHER CONSTRUCTION ACTIVITIES SHALL BE SEEDED ACCORDING TO THE SEED MIXES AND APPLICATION RATES SHOWN ON THIS SHEET.
- 2. ALL SEEDING AREAS SHALL BE PREPARED IN ACCORDANCE WITH THE SPECIFICATIONS. SEEDING AREAS NEED NOT BE CULTIVATED, BUT SHALL BE RAKED OR CHAINED TO ENSURE A FRIABLE SURFACE FREE OF SOIL CLUMPS LARGER THAN 2 INCHES IN DIAMETER.
- 3. FOR SEEDING AREAS OUTSIDE OF OHW, APPLICATION OF SEED SHALL BE FOLLOWED BY APPLICATION OF STRAW MULCH AT A RATE OF 2,000 LBS/ACRE.
- 4. FOR AREAS BELOW OHW THAT WILL BE PLANTED BY OTHERS, APPLY BARK OR WOODCHIP MULCH TO A DEPTH OF 3 INCHES.









NAME OR I	NITIALS AND DAT	Ε	GEOGRAPH	IIC INFORMATION
DESIGNED	JMS, ELD		LATITUDE	N047° 46' 7.64"
CHECKED	TBA		LONGITUDE	W120* 46' 7.76"
DRAWN	JGJ		TN/SC/RG	T26N/S7/R17E
CHECKED	JWS, GM		DATE	

NASON CREEK KAHLER REACH HABITAT IMPROVEMENT **PROJECT**

SEED SCHEDULES

23

20, 2021 100% PLANS - FOR CONSTRUCTION

Dec

SHEET **23** OF **23**