



CRP 722: High Street Drainage Project

High, Pine, Orchard and Main streets in Peshastin

Last Updated: Jan. 22, 2019



Project Vicinity Map

Funding Sources:

County Funds \$80,000

TOTAL: \$80,000

Project Number: County Road Project 722

Project Length: N/A

Basis for Project: Improve drainage conveyance

Construction: April 2019

Project Description: This locally funded project includes work to improve drainage conveyance in the Peshastin area. The existing concrete pipe that connects High Street to the existing mainline is failing and will be replaced. The proposed pipe location will run along the east side of Pine Street and connect to the existing mainline. The existing mainline is located along the southside of Main Street. The proposed connection to the mainline will be located 250 feet to the east of the current connection.

Status: Design complete. Project was awarded to Agostino Construction Inc. Construction is scheduled to start April 15, 2019, and to take 12 working days.

Traffic Impacts: Preliminary construction scheduled to take 12 working days. During construction the road will be at one lane with flaggers directing traffic.



Stormwater improvements to the drainage conveyance in the project area call for the abandoning of an existing failing culvert on High Street and the installation of six new drainage structures, 365 linear feet of culvert pipe, ditching and the construction of a paved swale.

